
Proposed Subdivision
The Fairways – Stage 1
Site Classification

Maison Dieu Road,
Singleton

NEW14P-0046-AG
16 January 2025



16 January 2025

McCloy Singleton Pty Ltd
Suite 2, Ground Floor, 317 Hunter Street
NEWCASTLE NSW 2300

Attention: Rylan Gibson

Dear Rylan,


**RE: PROPOSED SUBDIVISION – THE FAIRWAYS, STAGE 1
MAISON DIEU ROAD, SINGLETON
SITE CLASSIFICATION (LOTS 101 TO 130)**

Please find enclosed our geotechnical report for 'The Fairways Stage 1' residential subdivision, located at Maison Dieu Road, Singleton.

The report provides site classification with respect to reactive soils, in accordance with the requirements of AS2870-2011 '*Residential Slabs and Footings*', for Stage 1 (Lots 101 to 130), following completion of site regrade works.

If you have any questions regarding this report, please do not hesitate to contact Ben Edwards, Shannon Kelly, or the undersigned.

For and on behalf of Qualtest Laboratory (NSW) Pty Ltd

A handwritten signature in black ink, appearing to read 'Jason Lee', with a large, stylized loop at the end of the name.

Jason Lee
Principal Geotechnical Engineer

Table of Contents:

1.0	Introduction	1
2.0	Desktop Study	1
3.0	Field Work	1
4.0	Site Description	2
4.1	Site Regrade Works.....	2
4.2	Surface Conditions	3
4.3	Subsurface Conditions.....	6
5.0	Laboratory Testing	10
6.0	Site Classification to AS2870-2011	12
7.0	Limitations.....	13

Attachments:

Figures:	Figure AG1: Site Location Plan and Approximate Test Locations - North
	Figure AG2: Site Location Plan and Approximate Test Locations - South
Appendix A:	Results of Field Investigations
Appendix B:	Results of Laboratory Testing
Appendix C:	CSIRO Sheet BTF 18

1.0 Introduction

Qualtest Laboratory NSW Pty Ltd (Qualtest) is pleased to present this geotechnical site classification report to McCloy Singleton Pty Ltd (McCloy), for Stage 1 of the 'Fairways' residential subdivision, located at Maison Dieu Road, Singleton.

Based on Subdivision Plans provided, Stage 1 is understood to comprise of 30 residential lots (Lots 101 to 130).

The scope of work for the geotechnical investigation included site classification with respect to reactive soils, in accordance with the requirements of AS2870-2011 '*Residential Slabs and Footings*', for Stage 1 (Lots 101 to 130), following completion of site regrade works.

This report presents the results of the field work investigations and laboratory testing, and provides recommendations for the scope outlined above.

2.0 Desktop Study

The scope of work has included a review of the following reports completed by Qualtest or others, as noted below:

- Level 1 Site Re-grade Assessment Report, 'Fairways Estate Subdivision – Stage 1, Maison Dieu Rd, Singleton, (Qualtest Report Reference: MUS24P-0028-AD, dated 15 January 2025);
- Report on Preliminary Geotechnical Investigation conducted by Cardno Geotech Solutions (CGS), 'Proposed Gowrie Residential Development, Maison Dieu Rd, Singleton (report ref. 15121-002/0, May 2013); and,
- Geotechnical Assessment report by Qualtest, 'Proposed Subdivision, The Fairways Stages 1 & 2, Maison Dieu Road, Singleton (report ref. NEW14P-0046-AA, dated 18 June 2014).

This report includes selected results from the reports referenced above, to supplement information collected during the current investigations where applicable. Reference should be made to the reports outlined above for further details of site conditions, field work and laboratory testing conducted, site supervision, and testing carried out.

3.0 Field Work

Field work investigations were carried out on 5 November 2024 and 3 December 2024 and comprised of:

- DBYD search and visual check of proposed test locations for the presence of underground services;
- Site walkover to make observations of surface features at the property and in the immediate surrounding area;
- Excavation of 10 test pits (TPQ01 to TPQ10) using a 5 tonne excavator with a 300mm wide bucket. Test pits were terminated at depths of between 2.3m and 2.6m.
- Drilling 9 boreholes (BHQ11 to BHQ19) using a 2.7 tonne excavator equipped with a 300mm diameter auger attachment. Boreholes were terminated at depths of between 1.5m and 2.6m;
- Undisturbed samples (U50 tubes) and small bag samples were taken for subsequent laboratory testing; and,

- Test pits and boreholes were backfilled with the excavation spoil and compacted using the excavator bucket / auger and tracks.

Investigations were carried out by an experienced Geotechnical Engineer from Qualtest who located the test pits and boreholes, carried out the testing and sampling, produced field logs of the boreholes, and made observations of the site surface conditions.

Engineering logs of the test pits and boreholes are presented in Appendix A.

Approximate test pit and borehole locations are shown on the attached Figures AG1 & AG2. Test pits and boreholes were located in the field with assistance by KCE personnel with GPS rover and relative to existing site features.

4.0 Site Description

4.1 Site Regrade Works

Following an initial site visit, stripping assessment and recommendations performed on 16 July 2024 (Qualtest Site Record Form ref. MUS24P-0028-SR01, dated 24/07/24, and multiple subsequent visits throughout the project), site re-grading works within Stage 1, were conducted between 29 July 2024 and 13 December 2024.

Re-grade works included filling within all or portions of residential lots 101 to 105, 108 to 120, 124 and 125.

Prior to filling, re-grade areas were stripped of topsoil and unsuitable material to expose the suitable natural foundation profile. Preparation works were then performed, which consisted of fining, re-conditioning and re-compaction of the stripped surface, prior to filling with approved site fill to design finish levels.

Filling was generally performed using site material won from excavations within the cut areas and borrow areas within future stages of the development. The fill material could generally be described as mixtures of Residual (CI-CH) Sandy CLAY, medium to high plasticity, brown / red / grey/white in colour, with fine to coarse grained Sand and Gravel, along with Extremely Weathered (XW) Conglomerate / Sandstone, pale yellow / brown in colour, blended with minor quantities of on-site pale brown Colluvium

The approximate depth of fill placed ranged in the order of 0.1m to about 3.0m, with the deepest areas being within boundary of Lots 114 to 115 and the rear of lot 105. The approximate maximum depth of fill placed within each lot (excluding topsoil), was in the order of:

- Lots 101 to 104 – 0.1m to 1.6m;
- Lot 105 – 1.0m to 3.0m;
- Lots 108 to 118 – 0.1m to 1.8m;
- Lots 119 to 120 – 0.1m to 0.6m;
- Lots 124 to 125 – 0.1m to 0.6m.

The fill was compacted in maximum lifts of 0.3m thickness. Any unsuitable or deleterious material within the fill was removed by hand or mechanical means prior to final compaction of the material.

As the geotechnical testing authority engaged for the project, Qualtest state that the filling performed for the re-grade areas within Stage 1 (as detailed in the site regrade report, and shown approximately on Figures AG1 & AG2), was carried out to Level 1 criteria as defined in Clause 8.2 – Section 8 of AS3798-2007, 'Guidelines on Earthworks for Commercial and Residential Developments'.

The recommendations of this report are based on the understanding that any existing lot re-grade works are limited to the controlled earthworks supervised by Qualtest, and placement of low reactivity topsoil material such that total depth of topsoil and uncontrolled fill does not exceed 0.4m. Qualtest should be informed without delay if additional earthworks are known to have been carried out.

At the time of the field investigations, localised stockpiles were present on some lots. It is understood and expected that fill stockpiles will be removed prior to development on lots.

Topsoil had not been added to lots due to ongoing construction works with roads not constructed at the time of the field work. It is expected that at least 100mm of low to non-reactive Topsoil will be added to the lots.

4.2 Surface Conditions

The site comprises proposed Stage 1 of the Fairways subdivision, located off the southern side of Maison Dieu Road, Singleton, as shown on Figures AG1 & AG2.

The site is located in an area of moderately undulating topography. The site is positioned on three east trending convex spurs which extend from a prominent hill which rises to the west of the site. The spurs are separated by two gullies which cross the alignment of Road Number 1 and confluence nearby to the east, before turning to the south and draining towards the Hunter River which is located about 700m southeast of the site.

The majority of the site was judged to be moderately well drained following the existing regraded or natural ground surfaces.

The site was judged to have good trafficability by way of 4WD vehicle on the day of the field investigation.

Selected photographs of the site taken during the days of the site investigations are shown below.



Photograph 1: From near northern boundary of Lot 105, (approx. 15m north of BHQ19), facing south. Showing excavator at BHQ19 location.



Photograph 2: From near northern boundary of Lot 105, (approx. 15m north of BHQ19), facing southwest.



Photograph 3: From near centre of Lot 101, (near BHQ16), facing east.



Photograph 4: From near centre of Lot 101, (near BHQ16), facing south.



Photograph 5: From near southern boundary of Lot 104, (near BHQ18), facing north.



Photograph 6: From near southern boundary of Lot 104, (near BHQ18), facing east.



Photograph 7: From boundary of Lots 106 and Lot 107, (near TPQ01), facing south.



Photograph 8: From boundary of Lots 106 and Lot 107, (near TPQ01), facing west.



Photograph 9: From boundary of Lots 119 and Lot 120, (near TPQ03), facing south.



Photograph 10: From boundary of Lots 119 and Lot 120, (near TPQ03), facing west.



Photograph 11: From approx. 6m northeast of TPQ08, facing northwest.



Photograph 12: From approx. 6m northeast of TPQ08, facing north.



Photograph 13: From boundary of Lots 122 and Lot 123, (near BHQ11), facing north.



Photograph 14: From boundary of Lots 122 and Lot 123, (near BHQ11), facing east.




Photograph 15: From boundary of Lots 126 and Lot 127, (near BHQ13), facing south.



Photograph 16: From boundary of Lots 126 and Lot 127, (near BHQ13), facing west.



Photograph 17: From western boundary of Lot 130, (near BHQ15), facing northeast.



Photograph 18: From western boundary of Lot 130, (near BHQ15), facing southeast.

4.3 Subsurface Conditions

Reference to the 1:100,000 Newcastle Coalfield Regional Geology Series Sheet 9231 indicates the site to be underlain by the Mulbring Siltstone of the Maitland Group, and Saltwater Creek Formation of the Wittingham Coal Measures which are characterised by Siltstone, Sandstone, Claystone and Coal rock types.

Table 1 presents a summary of the typical soil types encountered on site during the field investigations, divided into representative geotechnical units.

Table 2 contains a summary of the distribution of the above geotechnical units at the test pit and borehole locations.

No groundwater was encountered in the boreholes or test pits during the limited time that they remained open on the day of the field investigation.

It should be noted that groundwater conditions can vary due to rainfall and other influences including regional groundwater flow, temperature, permeability, recharge areas, surface condition, and subsoil drainage.

TABLE 1 – SUMMARY OF GEOTECHNICAL UNITS AND SOIL TYPES

Unit	Soil Type	Description
1A	FILL – TOPSOIL	Not Encountered in test holes during current investigation.
1B	FILL – Controlled	<p>CLAY, Silty CLAY – medium to high plasticity, pale brown to dark brown, pale orange with pale grey to white, red-brown and grey-brown, with some silt and fine to medium grained sand.</p> <p>Gravelly Sandy CLAY / Gravelly Clayey SAND – mostly low to medium plasticity, pale brown, pale orange to orange, pale grey to white, red-brown, grey-brown, fine to coarse grained sand, fine to coarse grained angular to sub-angular rounded to sub-rounded gravel, with angular cobbles in places.</p> <p>Sandy CLAY - medium to high plasticity, dark brown to brown, grey-brown dark grey, pale grey to pale brown, and orange, fine to medium grained sand, trace fine to medium grained angular gravel in places.</p>
2	TOPSOIL	Gravelly Silty SAND - fine to coarse grained, grey, fines of low plasticity, fine grained angular gravel, root affected.
3	ALLUVIUM	Not Encountered in test holes during current investigation.
4	RESIDUAL SOIL	<p>CLAY, Silty CLAY, Sandy Silty CLAY – medium to high plasticity, brown, pale grey to white, orange to red-brown, pale orange, grey-brown, and dark grey, with fine to coarse grained sand, trace fine to medium grained sub-rounded to angular gravel in places.</p> <p>Sandy CLAY - medium to high plasticity, dark brown, dark grey, pale brown, red-brown, grey-brown, pale grey and orange, fine to coarse grained sand, trace fine to medium grained subrounded to sub-angular gravel.</p> <p>Sandy CLAY / Clayey SAND – low to medium plasticity, pale brown, pale orange and pale grey to white, fine to coarse grained sand, with fine to medium grained angular gravel in places.</p> <p>Borderline extremely weathered rock in places. With extremely weathered to highly weathered bands in places.</p>
5	EXTREMELY WEATHERED (XW) ROCK with soil properties	Not Encountered in test holes during current investigation.
6	EXTREMELY TO HIGHLY WEATHERED (HW) ROCK	Sandy SILTSTONE - fine to medium grained, grey, with some Extremely Weathered bands. Mostly of estimated very low rock strength within depth of investigation.

TABLE 2 – SUMMARY OF GEOTECHNICAL UNITS ENCOUNTERED AT TEST LOCATIONS

Location	UNIT 1A Fill - Topsoil	UNIT 1B Fill - Controlled	UNIT 2 Topsoil	UNIT 3 Alluvium	Unit 4 Residual Soil	Unit 5 XW Rock	Unit 6 XW to HW Rock
	Depth (m)						
TPQ01	-	-	-	-	0.00 - 2.30	-	-
TPQ02	-	0.00 - 1.00	-	-	1.00 - 2.30	-	-
TPQ03	-	-	-	-	0.00 - 2.30	-	-
TPQ04	-	-	-	-	0.00 - 2.50^	-	-
TPQ05	-	0.00 - 1.20	-	-	1.20 - 2.40^	-	-
TPQ06	-	-	-	-	0.00 - 2.30	-	-
TPQ07	-	0.00 - 0.65	-	-	0.65 - 2.50	-	-
TPQ08	-	0.00 - 1.60	-	-	1.60 - 2.60	-	-
TPQ09	-	0.00 - 0.70	-	-	0.70 - 2.50	-	-
TPQ10	-	-	0.00 - 0.15	-	0.15 - 2.50	-	-
BHQ11	-	-	0.00 - 0.15	-	0.15 - 2.60	-	-
BHQ12	-	0.00 - 0.60	-	-	0.60 - 2.60	-	-
BHQ13	-	-	-	-	0.00 - 0.80	-	0.80 - 1.70^
BHQ14	-	-	-	-	0.00 - 2.50	-	2.50 - 2.60
BHQ15	-	-	-	-	0.00 - 0.80	-	0.80 - 1.50^
BHQ16	-	0.00 - 1.30	-	-	1.30 - 2.10*	-	-
BHQ17	-	0.00 - 1.70*	-	-	-	-	-
BHQ18	-	0.00 - 1.50	-	-	1.50 - 2.60^	-	-
BHQ19	-	0.00 - 2.60	-	-	-	-	-

Location	UNIT 1A Fill - Topsoil	UNIT 1B Fill - Controlled	UNIT 2 Topsoil	UNIT 3 Alluvium	Unit 4 Residual Soil	Unit 5 XW Rock	Unit 6 XW to HW Rock
	Depth (m)						
Previous investigation (Ref. NEW14P-0046-AA, dated 18/06/2014) – Prior to Site Regrade / Site Filling							
TP1-1	-	-	0.00 - 0.10	-	0.10 - 2.40	2.40 - 2.60	-
TP1-2	-	-	0.00 - 0.15	-	0.15 - 2.20	-	-
TP1-3	-	-	0.00 - 0.10	-	0.10 - 2.10	-	-
TP1-4	-	-	0.00 - 0.15	-	0.15 - 2.20	-	-
TP1-5	-	-	0.00 - 0.10	-	0.10 - 2.10	-	-
TP1-6	-	-	0.00 - 0.15	-	0.15 - 0.60	-	0.60 - 2.00
TP1-7	-	-	0.00 - 0.10	-	0.10 - 0.90	-	0.90 - 1.90
TP2-1	-	-	0.00 - 0.15	-	0.15 - 1.00	-	1.00 - 1.85
TP2-2	-	-	0.00 - 0.10	-	0.10 - 0.90	-	0.90 - 1.90
CGS Test Pits – Preliminary Geotechnical Investigations (Ref: 15121-002/0, May 2013) – Prior to Site Regrade / Site Filling							
TP001			0.00 - 0.10	-	0.00 - 2.20	2.20 - 5.40	5.40 - 5.80
TP003			0.00 - 0.10	0.10 - 1.50	1.50 - 3.80	-	-
TP004			0.00 - 0.10	-	0.10 - 2.20	-	2.20 - 3.30
Notes:	^ = Slow to very slow progress of 2.7 tonne excavator. * = Refusal or Practical refusal of 2.7 tonne excavator.						

5.0 Laboratory Testing

Samples collected during the field investigations were returned to our NATA accredited Newcastle Laboratory for testing which comprised of:

- (34 no.) Shrink / Swell tests; and,
- (2 no.) Atterberg Limits tests.

Proposed shrink/swell testing for two samples were replaced by Atterberg Limits classification tests due to the friable nature of the site soils.

Results of the laboratory testing are presented in Appendix B, with a summary of the test results presented in Table 3 and Table 4.

The tables also include a summary of laboratory testing information where applicable from the previous Geotechnical Assessment carried out by Qualtest.

TABLE 3 – SUMMARY OF SHRINK/SWELL TESTING RESULTS

Location	Depth (m)	Material Description	I _{ss} (%)
Current Investigation			
TPQ01	0.40 - 0.58	(CH) CLAY	2.6
TPQ01	1.00 - 1.20	(CH) Silty CLAY	2.6
TPQ02	0.40 - 0.55	FILL: (CH) CLAY	3.0
TPQ02	1.10 - 1.30	(CH) CLAY	2.1
TPQ03	0.40 - 0.55	(CI) Sandy CLAY	0.2
TPQ03	1.40 - 1.50	(CI) Sandy CLAY	0.4
TPQ04	0.30 - 0.46	(CI) Sandy CLAY	1.3
TPQ04	1.00 - 1.15	(CI) Sandy CLAY	0.8
TPQ05	0.50 - 0.67	FILL: (CH) CLAY	3.7
TPQ05	1.30 - 1.45	(CH) Sandy Clay	1.3
TPQ06	0.50 - 0.65	(CH) CLAY	0.6
TPQ06	1.40 - 1.55	(CH) CLAY	0.9
TPQ07	0.40 - 0.57	FILL: (CI) Silty CLAY	3.0
TPQ07	0.80 - 1.00	(CI) Sandy CLAY	1.7
TPQ08	1.70 - 2.00	(CH) CLAY	1.1
TPQ09	0.50 - 0.65	FILL: (CH) Sandy CLAY	2.1
TPQ09	0.70 - 0.90	(CH) Sand CLAY	1.4
TPQ10	0.30 - 0.57	(CH) Sandy CLAY	2.5
TPQ10	1.00 - 1.15	(CL) Sandy CLAY	1.7
BHQ11	0.40 – 0.60	(CH) CLAY	1.9

BHQ11	1.00 – 1.15	(CH) CLAY	1.8
BHQ12	0.45 – 0.60	FILL: (CI) Sandy CLAY	1.2
BHQ12	1.10 – 1.30	(CH) CLAY	1.2
BHQ13	0.50 – 0.64	(CI) Sandy Silty CLAY	1.9
BHQ14	0.40 – 0.56	(CI) Sandy CLAY	2.0
BHQ15	0.60 – 0.75	(CI) Sandy Silty CLAY	0.8
BHQ16	0.50 – 0.65	FILL: (CI) Sandy CLAY	1.9
BHQ16	1.00 – 1.15	FILL: (CI) Sandy CLAY	1.3
BHQ17	0.50 – 0.65	FILL: (CI) Sandy CLAY	1.1
BHQ17	1.00 – 1.20	FILL: (CI) Sandy CLAY	1.9
BHQ18	0.50 – 0.65	FILL: (CI) Gravelly Sandy CLAY	1.9
BHQ18	1.00 – 1.15	FILL: (CI) Gravelly Sandy CLAY	0.9
BHQ19	0.80 – 0.95	FILL: (CI) Sandy CLAY	1.7
BHQ19	1.40 – 1.60	FILL: (CI) Sandy CLAY	2.1
Previous investigation (Ref. NEW14P-0046-AA, dated 18/06/2014)			
TP1-1	0.30 - 0.60	(CH) Sandy CLAY	1.3
TP1-2	0.60 - 0.90	(CH) Sandy CLAY / Clayey SAND	0.7
TP1-4	0.30 - 0.50	(CH) CLAY / Sandy CLAY	3.7
TP1-5	0.50 - 0.75	(CH) CLAY / Sandy CLAY	3.2
TP1-6	0.20 - 0.45	(CH) CLAY / Sandy CLAY	3.4
TP2-2	0.60 - 0.80	(CL) Sandy CLAY / CLAY	1.5
TP2-3	0.20 - 0.45	(CH) CLAY	1.6
TP2-5	0.30 - 0.50	(CH) CLAY / Sandy CLAY	2.2
CGS Test Pits – Preliminary Geotechnical Investigations (Ref: 15121-002/0, May 2013)			
TP001	0.70 - 1.01	Sandy CLAY	0.4
TP004	0.40 - 0.55	Sandy Silty CLAY	2.9
TP004	0.80 - 1.10	Sandy CLAY	3.0

TABLE 4 – SUMMARY OF ATTERBERG LIMITS TESTING RESULTS

Location	Depth (m)	Material Description	Liquid Limit (%)	Plasticity Index (%)	Linear Shrinkage (%)
TPQ08	0.40 - 0.55	FILL: (CL) Gravelly Sandy CLAY / Clayey SAND	35	15	5.0
BHQ14	1.10 – 1.30	(CI) Silty CLAY	48	32	12.5

6.0 Site Classification to AS2870-2011

Based on the results of the field work and laboratory testing carried out, proposed residential lots located within The Fairways Stage 1 at Maison Dieu Road, Singleton, as shown on Figure AG1, are classified in their current condition in accordance with AS2870-2011 'Residential Slabs and Footings', as shown in Table 5.

TABLE 5 – SITE CLASSIFICATION TO AS2870-2011

Stage No.	Lot Numbers	Site Classification
1	106, 107, 121 to 123, 126 to 130	H1-D
	101 to 105, 108 to 120, 124, 125	H2-D

A characteristic free surface movement of 40mm to 60mm is estimated for lots classified as **Class 'H1'** in their existing condition.

A characteristic free surface movement of 60mm to 75mm is estimated for lots classified as **Class 'H2'** in their existing condition.

The effects of changes to the soil profile by additional cutting and filling and the effects of past and future trees should be considered in selection of the design value for differential movement.

If site re-grading works involving cutting or filling are performed after the date of this assessment, the classification may change and further advice should be sought.

Final site classification will be dependent on a number of factors, including depth of topsoil, depth of fill and residual soil, reactivity of the natural soil and any fill material placed, and the level of supervision carried out. Re-classification of lots should be confirmed by the geotechnical authority at the time of construction following any site re-grade works.

Footings for the proposed development should be designed and constructed in accordance with the requirements of AS2870-2011.

The classification presented above assumes that:

- All footings are founded in controlled fill (if applicable) or in the residual clayey soils or rock below all non-controlled fill, topsoil material and root zones, and fill under slab panels meets the requirements of AS2870-2011, in particular, the root zone must be removed prior to the placement of fill materials beneath slabs.
- The performance expectations set out in Appendix B of AS2870-2011 are acceptable, and that site foundation maintenance is undertaken to avoid extremes of wetting and drying;
- Footings are to be founded outside of or below all zones of influence resulting from existing or future service trenches.
- The constructional and architectural requirements for reactive clay sites set out in AS2870-2011 are followed.

- Adherence to the detailing requirement outlined in Section 5 of AS2870-2011 '*Residential Slabs and Footings*' is essential, in particular Section 5.6, '*Additional requirements for Classes M, H1, H2 and E sites*' including architectural restrictions, plumbing and drainage requirements.
- Site maintenance complies with the provisions of CSIRO Sheet BTF 18, "*Foundation Maintenance and Footing Performance: A Homeowner's Guide*", a copy of which is attached in Appendix C.

All structural elements on all lots should be supported on footings founded beneath all uncontrolled fill, layers of inadequate bearing capacity, soft/loose, wet or other potentially deleterious material.

If any localised areas of uncontrolled fill of depths greater than 0.4m are encountered during construction, footings should be designed in accordance with engineering principles for Class 'P' sites.

7.0 Limitations

This report comprises the results of an investigation carried out for a specific purpose and client as defined in the document. The report should not be used by other parties or for purposes or projects other than those assumed and stated within the report, as it may not contain adequate or appropriate information for applications other than those assumed or advised at the time of its preparation. The contents of the report are for the sole use of the client and no responsibility or liability will be accepted to any third party. The report should not be reproduced either in part or in full, without the express permission of Qualtest.

Geotechnical site investigation is based on data collection, judgment, experience, and opinion. By its nature, it is less exact than other engineering disciplines. The findings presented in the report and used as the basis for recommendations presented herein were obtained using normal, industry accepted geotechnical design practices and standards. To our knowledge, they represent a reasonable interpretation of the general conditions of the site. Under no circumstances, however, can it be considered that these findings represent the actual state of the site at all points.

The recommended depth and properties of any soil, rock, groundwater, or other material referred to in this report is an engineering estimate based on the information available at the time of its writing. The estimate is influenced and limited by the fieldwork method and testing carried out in the site investigation, and other relevant information as has been made available. In cases where information has been provided to Qualtest for the purposes of preparing this report, it has been assumed that the information is accurate and appropriate for such use. No responsibility is accepted by Qualtest for inaccuracies within any data supplied by others.


The extent of testing associated with this assessment is limited to discrete test locations. It should be noted that subsurface conditions between and away from the test locations may be different to those observed during the field work and used as the basis of the recommendations contained in this report.

If site conditions encountered during construction differ from those given in this report, further advice should be sought without delay.

This report alone should not be used by contractors as the basis for preparation of tender documents or project estimates. Contractors using this report as a basis for preparation of tender documents should avail themselves of all relevant background information regarding the site before deciding on selection of construction materials and equipment.

If you have any further questions regarding this report, please do not hesitate to contact Ben Edwards, Shannon Kelly, or the undersigned.

For and on behalf of Qualtest Laboratory (NSW) Pty Ltd.


A handwritten signature in black ink, appearing to read "Jason Lee". The signature is written in a cursive, flowing style.

Jason Lee
Principal Geotechnical Engineer

FIGURES




**Figure AG1: Site Location Plan and
Approximate Test Locations – North**

**Figure AG2: Site Location Plan and
Approximate Test Locations – South**



Based on ACOR Consultants Pty Ltd drawing (Ref: NSW220583, C05-002, E, dated 13.03.24)


LEGEND:

-  Approximate borehole location.
-  Approximate test pit location (Qualtest 2014, Cardno 2013).
-  Approximate extent of site regrade works.







Client:	MCCLOY SINGLETON PTY LTD
Project:	PROPOSED RESIDENTIAL SUBDIVISION - THE FAIRWAYS, STAGE 1
Location:	LOT 1221 DP599260, MAISON DIEU ROAD, SINGLETON
Title:	SITE LOCATION PLAN & APPROXIMATE TEST LOCATIONS - NORTH


Drawing No:	FIGURE AG1
Project No:	NEW14P-0046
Scale:	N.T.S.
Date:	16/01/2025



LEGEND:

-  Approximate test pit location (2024).
-  Approximate borehole location (2024).
-  Approximate test pit location (Qualtest 2014, Cardno 2013).
-  Approximate extent of site regrade works.

Based on ACOR Consultants Pty Ltd drawing (Ref: Project No: NSW220583, Drawing No: C05-002, Issue: E, dated 26.11.24)

	Client:	MCCLOY SINGLETON PTY LTD	Drawing No:	FIGURE AG2
	Project:	PROPOSED RESIDENTIAL SUBDIVISION - THE FAIRWAYS, STAGE 1	Project No:	NEW14P-0046
	Location:	LOT 1221 DP599260, MAISON DIEU ROAD, SINGLETON	Scale:	N.T.S.
	Title:	SITE LOCATION PLAN & APPROXIMATE TEST LOCATIONS - SOUTH	Date:	16/01/2025

APPENDIX A:

Results of Field Investigations



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ01

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	
E	Not Encountered	0.40m			CH	CLAY - medium to high plasticity, pale orange, with pale grey to white, with silt, trace fine grained sand.	M < w _p	H	HP	>600	RESIDUAL SOIL
		U50	0.5						HP	500	
		0.58m							HP	550	
		1.00m	1.0						HP	550	
		U50	1.20m						HP	580	
									HP	500	
									HP	>600	
									HP	550	
									HP	530	
									HP	550	
			2.30m			Hole Terminated at 2.30 m					

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density		
V Very Loose	Density Index <15%	
L Loose	Density Index 15 - 35%	
MD Medium Dense	Density Index 35 - 65%	
D Dense	Density Index 65 - 85%	
VD Very Dense	Density Index 85 - 100%	

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO: TPQ02

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR
 TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

SURFACE RL:
 DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations						
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result					
E	Not Encountered	0.40m		0.5		CI	FILL: Gravelly Sandy CLAY - medium plasticity, pale grey to white, with pale orange to orange to red-brown, fine to coarse (mostly fine) grained sand, fine to coarse grained angular to sub-angular gravel. FILL: CLAY - medium to high plasticity, dark brown, with grey-brown, with fine to medium grained sand.	M < w _p	H	HP	450	FILL: CONTROLLED					
		U50 0.55m													FILL: CONTROLLED / POSSIBLE ALLUVIUM		
		1.10m		1.0		CH	CLAY - medium to high plasticity, red-brown to grey-brown, trace fine to coarse grained sand, trace fine to medium grained sub-rounded gravel, trace rootlets.	M > w _p		HP	210	RESIDUAL SOIL					
		U50 1.30m															
				2.0		CL	Silty Sandy CLAY/Clayey SAND - low to medium plasticity, pale brown, trace pale orange and pale grey, fine grained sand.	M < w _p	H / Fb	HP	420						
				2.5			Hole Terminated at 2.30 m										

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Consistency VS Very Soft <25 S Soft 25 - 50 F Firm 50 - 100 St Stiff 100 - 200 VSt Very Stiff 200 - 400 H Hard >400 Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
		Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ03

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
E	Not Encountered	0.40m		0.5		Cl	Sandy CLAY - medium plasticity, dark brown, with pale grey and orange, fine to coarse (mostly fine) grained sand, trace fine to medium grained sub-angular gravel.	M < w _p	H	HP	>600	RESIDUAL SOIL
		U50 0.55m								HP	>600	
		1.40m								HP	>600	
		U50 1.50m								HP	>600	
										HP	>600	
				2.0								
				2.30m			Hole Terminated at 2.30 m					
				2.5								

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition	
VS	Very Soft	<25	D	Dry
S	Soft	25 - 50	M	Moist
F	Firm	50 - 100	W	Wet
St	Stiff	100 - 200	W _p	Plastic Limit
VSt	Very Stiff	200 - 400	W _L	Liquid Limit
H	Hard	>400		
Fb	Friable			
Density		V	Density Index <15%	
L	Loose		Density Index 15 - 35%	
MD	Medium Dense		Density Index 35 - 65%	
D	Dense		Density Index 65 - 85%	
VD	Very Dense		Density Index 85 - 100%	

OT.LIB.1.1.GLB.Log.NON-CORED.BOREHOLE - TEST PIT_NEW14P-0046.LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ04

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
E	Not Encountered	0.30m		0.5		Cl	Sandy CLAY - medium plasticity, dark brown, with pale grey and orange, fine to coarse (mostly fine) grained sand, trace fine to medium grained sub-angular gravel.	M < w _p	H	HP	>600	RESIDUAL SOIL
		U50 0.46m								HP	>600	
		1.00m		1.0						HP	>600	
		U50 1.15m								HP	>600	
		2.0								HP	>600	
				2.5			Hole Terminated at 2.50 m Slow progress					

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₅₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO: TPQ05

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR
 TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

SURFACE RL:
 DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations					
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result				
E	Not Encountered	0.20m		0.5		CL	FILL: Gravelly Sandy CLAY - low to medium plasticity, pale brown, with pale orange and pale grey to white, fine to coarse (mostly fine) grained sand, fine to coarse grained angular gravel, with angular cobbles.	M < w _p	H	HP	550					
		D								HP	>600					
		0.40m								0.90m	CH	FILL: CLAY - medium to high plasticity, red-brown and grey-brown.	M > w _p	VSt	HP	380
		0.50m													HP	380
		U50													HP	380
		0.67m													HP	380
1.30m		1.5	CH	Sandy CLAY - medium to high plasticity, red-brown and dark grey, fine to coarse (mostly fine) grained sand, trace fine to medium grained sub-rounded gravel.	M < w _p	H	HP	550								
U50							HP	>600								
		1.45m		2.0		CH			HP	>600						
				2.40m						HP	>600					
				2.5			Hole Terminated at 2.40 m Slow progress									

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		

Density	Density Index
V Very Loose	<15%
L Loose	15 - 35%
MD Medium Dense	35 - 65%
D Dense	65 - 85%
VD Very Dense	85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO: TPQ06

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR
 TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

SURFACE RL:
 DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
E	Not Encountered	U50 0.65m		0.5		CH	CLAY - medium to high plasticity, brown and dark grey, with pale brown, with fine to coarse (mostly fine) grained sand.	M < w _p	H	HP	580	RESIDUAL SOIL	
		U50 0.50m		0.5						HP	550		
		U50 1.55m		1.5						HP	>600		
		U50 1.40m		1.4						HP	>600		
				2.0									
				2.30m			Hole Terminated at 2.30 m						
				2.5									

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)
VS Very Soft	<25
S Soft	25 - 50
F Firm	50 - 100
St Stiff	100 - 200
VSt Very Stiff	200 - 400
H Hard	>400
Fb Friable	

Moisture Condition
D Dry
M Moist
W Wet
W _p Plastic Limit
W _L Liquid Limit

Density	Density Index
V Very Loose	<15%
L Loose	15 - 35%
MD Medium Dense	35 - 65%
D Dense	65 - 85%
VD Very Dense	85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ07

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations				
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result			
E	Not Encountered	0.40m		0.5	[Cross-hatched pattern]	CI	FILL: Silty CLAY - medium plasticity, pale brown and pale grey to white, with orange to red-brown, trace fine grained sand.	M ~ W _p	H	HP	480	FILL: CONTROLLED			
		U50 0.57m								HP	450				
		0.80m		1.0	[Diagonal lines pattern]	CI	Sandy CLAY - medium plasticity, dark brown and dark grey, trace pale brown, fine grained sand.	M < W _p	H	HP	380		RESIDUAL SOIL		
			U50 1.00m								HP			380	
		1.40m		1.5	[Diagonal lines pattern]	CI		M < W _p	H	HP	380				
			U50 1.50m								HP			480	
						2.0									
						2.5									

Hole Terminated at 2.50 m

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense	D Dense	Density Index 35 - 65%
VD Very Dense	D Dense	Density Index 65 - 85%
		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ08

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
E	Not Encountered	0.40m		0.5		CL	FILL: Gravelly Sandy CLAY/Gravelly Clayey SAND - low to medium plasticity, pale brown, with pale orange and pale grey, trace fine to medium grained angular gravel.	M < Wp	H / Fb	HP	>600	FILL: CONTROLLED
		U50 0.55m	HP							>600		
		1.20m	HP							>600		
		U50 1.35m	HP							>600		
		1.70m	HP							>600		
		U50 2.00m	HP							330		
		2.10m	HP							380		
D 2.30m	HP	550										
				2.0		CH	CLAY - medium to high plasticity, brown and pale grey to white, with orange to red-brown, with fine grained sand, trace tree roots, trace fine to medium grained angular gravel.	M > Wp	VSt	HP	480	RESIDUAL SOIL
				2.5		CH	CLAY - medium to high plasticity, brown and dark grey, with orange to red-brown.	M < Wp	H	HP	420	
							Hole Terminated at 2.60 m					

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense	D Dense	Density Index 35 - 65%
VD Very Dense	D Dense	Density Index 65 - 85%
		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ09

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations								
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result							
E	Not Encountered	0.20m		0.5		CL	FILL: Gravelly Sandy CLAY/Gravelly Clayey SAND - low to medium plasticity, pale brown, with pale orange and pale grey, trace fine to medium grained angular gravel.	M < Wp	H	HP	550	FILL: CONTROLLED							
		D	0.40m								HP		480						
		U50	0.50m								CH		FILL: Sandy CLAY - medium to high plasticity, dark brown and dark grey, with pale brown, trace fine to medium grained sand.	H	HP	500	FILL: CONTROLLED / POSSIBLE RESIDUAL SOIL		
		0.65m																	
		0.70m																	
		U50	0.90m								CH		Sandy CLAY - medium to high plasticity, dark brown and dark grey, with brown, fine grained sand.	M > Wp	VSt	HP	>600	RESIDUAL SOIL	
		1.40m	U50														1.55m		500
																			380
																			350
													2.0						HP
			2.5							HP	380								
										HP	450								
							Hole Terminated at 2.50 m	M ~ Wp	H										

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense		Density Index 35 - 65%
VD Very Dense		Density Index 65 - 85%
		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:51 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - TEST PIT

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

TEST PIT NO:

TPQ10

PAGE:

1 OF 1

JOB NO:

NEW14P-0046

LOGGED BY:

BE

DATE:

5/11/24

EQUIPMENT TYPE: 5 TONNE EXCAVATOR

SURFACE RL:

TEST PIT LENGTH: 2.0 m WIDTH: 0.3 m

DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
E	Not Encountered			0.30m		SM	TOPSOIL: Gravelly Silty SAND - fine to coarse grained, grey, fines of low plasticity, fine grained angular gravel, root affected.	M				TOPSOIL
		U50		0.57m		CH	Sandy CLAY - medium to high plasticity, red-brown and grey-brown, fine grained sand.		H	HP	>600	RESIDUAL SOIL
		U50		1.00m		CL	Sandy CLAY - low to medium plasticity, pale orange and pale grey to white, fine to coarse (mostly fine) grained sand, with fine to medium grained angular gravel.	M < w _p	H / Fb	HP	>600	
		U50		1.15m	Increasing in gravel content.							
				2.0			Highly weathered SHALE band - approximately 50mm thick, fractured. Becoming medium to high plasticity, with white.	M > w _p	VSt	HP	230	
				2.5			Hole Terminated at 2.50 m			HP	220	

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense	D Dense	Density Index 35 - 65%
VD Very Dense	D Dense	Density Index 65 - 85%
		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:51 10.03.00.09 Datgel Lab and In Situ Tool

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered					SM	TOPSOIL: Gravelly Silty SAND - fine to coarse grained, grey, fines of low plasticity, fine grained angular gravel, root affected.	M < w _p				TOPSOIL	
		0.40m					CLAY - medium to high plasticity, brown to grey-brown.			HP	220	RESIDUAL SOIL	
		U50 0.60m			0.5		CH	Red-brown, with grey-brown.	M > w _p	VSt	HP	250	
		1.00m			1.0						HP	280	
		U50 1.15m 1.20m			1.20m		CL	Silty CLAY - low to medium plasticity, pale orange, trace pale grey to white, with extremely weathered to highly weathered bands.	M < w _p	H / Fb	HP	350	RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
		D 1.40m			1.5								
				2.0									
				2.5									
				2.60m			Hole Terminated at 2.60 m						

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		

Density		Density Index
V	Very Loose	<15%
L	Loose	15 - 35%
MD	Medium Dense	35 - 65%
D	Dense	65 - 85%
VD	Very Dense	85 - 100%



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

BOREHOLE NO: **BHQ12**

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT SURFACE RL:
BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.45m		0.5	[Cross-hatched pattern]	CI	FILL: Sandy CLAY - medium plasticity, pale grey to pale brown, with orange.	M < W _p	H	HP	>600	FILL: CONTROLLED RESIDUAL SOIL
		U50 0.60m		0.60m								
		0.85m		1.0	[Diagonal hatched pattern]	CH	CLAY - medium to high plasticity, brown to grey-brown. Red-brown, with grey-brown.	M > W _p	VSt	HP	210	
		U50 1.00m		HP						310		
		1.10m		HP						410		
		U50 1.30m		HP						480		
			1.5						HP	510		
			2.0							HP	480	
			2.5							HP	480	
				2.60m			Hole Terminated at 2.60 m					

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₅₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		

Density		Density Index
V	Very Loose	<15%
L	Loose	15 - 35%
MD	Medium Dense	35 - 65%
D	Dense	65 - 85%
VD	Very Dense	85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:49 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

BOREHOLE NO: **BHQ13**

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT SURFACE RL:
BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.50m		0.5		Cl	Sandy Silty CLAY - medium plasticity, pale orange, with pale grey.	M < w _p	H	HP	>600	RESIDUAL SOIL
		U50 0.64m								HP	>600	
				0.80m			Sandy SILTSTONE - fine to medium grained, grey, estimated very low strength, trace extremely weathered bands.	D		HP	>600	
				1.0								
				1.5								
				1.70m								
				2.0								
				2.5								
							Hole Terminated at 1.70 m Slow progress					

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₅₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST.PIT_NEW14P-0046.LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:49 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BHQ14

CLIENT: MCCLOY SINGLETON PTY LTD

PAGE: 1 OF 1

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

JOB NO: NEW14P-0046

LOCATION: MAISON DIEU ROAD, SINGLETON

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations										
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result									
AD/T	Not Encountered	0.40m		0.5		CI	Sandy CLAY - medium plasticity, red-brown, with pale orange and pale grey, fine to medium grained sand.	M < W _p	H	HP	480	RESIDUAL SOIL									
		U50								HP	400										
		0.56m								M > W _p	VSt		HP	350							
													HP	350							
		0.90m								1.0			D	Silty CLAY - medium plasticity, pale orange, with pale grey.	M < W _p	H	HP	410	RESIDUAL SOIL / EXTREMELY WEATHERED ROCK		
		U50															HP	380			
		1.05m															M > W _p	VSt		HP	300
		1.10m																		HP	280
		U50															M > W _p	VSt		HP	220
		1.30m																		HP	220
										2.50m			2.50m			Sandy SILTSTONE - fine to medium grained, grey, estimated very low strength, trace extremely weathered bands.	D			EXTREMELY TO HIGHLY WEATHERED ROCK	
													2.60m			Hole Terminated at 2.60 m					

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₃₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Consistency VS Very Soft <25 S Soft 25 - 50 F Firm 50 - 100 St Stiff 100 - 200 VSt Very Stiff 200 - 400 H Hard >400 Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
		Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:49 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BHQ15

CLIENT: MCCLOY SINGLETON PTY LTD

PAGE: 1 OF 1

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

JOB NO: NEW14P-0046

LOCATION: MAISON DIEU ROAD, SINGLETON

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.60m		0.5		Cl	Sandy Silty CLAY - medium plasticity, orange, with pale grey, fine grained sand.	M < w _p	H / Fb	HP	>600	RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
		U50 0.75m								HP	>600	
				1.0			Sandy SILTSTONE - grey, fine to medium grained sand, estimated very low strength, trace extremely weathered bands.			HP	>600	
				1.5			Hole Terminated at 1.50 m Very slow progress					

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool

LEGEND: Water Water Level (Date and time shown) Water Inflow Water Outflow Strata Changes Gradational or transitional strata Definitive or distinct strata change	Notes, Samples and Tests U ₅₀ 50mm Diameter tube sample CBR Bulk sample for CBR testing E Environmental sample (Glass jar, sealed and chilled on site) ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled) B Bulk Sample	Consistency VS Very Soft <25 S Soft 25 - 50 F Firm 50 - 100 St Stiff 100 - 200 VSt Very Stiff 200 - 400 H Hard >400 Fb Friable	UCS (kPa) <25 25 - 50 50 - 100 100 - 200 200 - 400 >400	Moisture Condition D Dry M Moist W Wet W _p Plastic Limit W _L Liquid Limit
	Field Tests PID Photoionisation detector reading (ppm) DCP(x-y) Dynamic penetrometer test (test depth interval shown) HP Hand Penetrometer test (UCS kPa)	Density V Very Loose L Loose MD Medium Dense D Dense VD Very Dense	Density Index <15% Density Index 15 - 35% Density Index 35 - 65% Density Index 65 - 85% Density Index 85 - 100%	



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

BOREHOLE NO: **BHQ16**

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT SURFACE RL:
BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	0.50m		0.5		CI	FILL: Sandy CLAY - medium plasticity, brown, with pale grey and pale orange, fine to medium grained sand, with some fine to medium grained angular gravel.	M > W _p	VSt	HP	320	FILL: CONTROLLED	
		U50 0.65m									HP		350
		1.00m		1.0							HP		300
		U50 1.15m									HP		220
		1.60m		1.5		CH	CLAY - medium to high plasticity, brown, with some grey-brown.			HP	220	RESIDUAL SOIL	
		1.90m		2.0						HP	230		
				2.10m			Hole Terminated at 2.10 m Refusal on possible Rock						

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		

Density	Density Index
V Very Loose	<15%
L Loose	15 - 35%
MD Medium Dense	35 - 65%
D Dense	65 - 85%
VD Very Dense	85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BHQ17

CLIENT: MCCLOY SINGLETON PTY LTD

PAGE: 1 OF 1

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

JOB NO: NEW14P-0046

LOCATION: MAISON DIEU ROAD, SINGLETON

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT **SURFACE RL:**
BOREHOLE DIAMETER: 300 mm **DATUM:**

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations	
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result
AD/T	Not Encountered	0.50m		0.5		CI	FILL: Sandy CLAY - medium plasticity, brown, with pale grey and pale orange, fine to medium grained sand, with some fine to medium grained angular gravel.	M > w _p	VSt	HP	350	FILL: CONTROLLED
		U50 0.65m								HP	380	
		1.00m		1.0						HP	350	
		U50 1.20m								HP	300	
				1.5						HP	380	
				1.70m		Hole Terminated at 1.70 m Refusal on possible weathered rock						
				2.0								
				2.5								

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₅₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)	Moisture Condition
VS	Very Soft	<25	D Dry
S	Soft	25 - 50	M Moist
F	Firm	50 - 100	W Wet
St	Stiff	100 - 200	W _p Plastic Limit
VSt	Very Stiff	200 - 400	W _L Liquid Limit
H	Hard	>400	
Fb	Friable		
Density			
V	Very Loose		Density Index <15%
L	Loose		Density Index 15 - 35%
MD	Medium Dense		Density Index 35 - 65%
D	Dense		Density Index 65 - 85%
VD	Very Dense		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST.PIT_NEW14P-0046.LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

BOREHOLE NO: **BHQ18**

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT SURFACE RL:
BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result	
AD/T	Not Encountered	U50	0.65m	0.50m		CI	FILL: Gravelly Sandy CLAY - medium plasticity, brown to grey-brown, fine to medium grained sand, fine to medium grained angular gravel.	M > W _p	VSt	HP	350	FILL: CONTROLLED	
		U50	0.65m	0.50m						HP	380		
		U50	1.15m	1.00m						HP	280		
		U50	1.15m	1.00m						HP	300		
		U50	1.15m	1.00m						HP	280		
		U50	1.15m	1.00m						HP	250		RESIDUAL SOIL
		U50	1.15m	1.00m						HP	400		
		U50	1.15m	1.00m						HP	410		
		U50	1.15m	1.00m						HP	410		
											1.50m		
				2.0		CI	With extremely weathered to highly weathered bands.						
				2.60m		CI	Hole Terminated at 2.60 m Slow progress						

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₃₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)	Moisture Condition
VS Very Soft	<25	D Dry
S Soft	25 - 50	M Moist
F Firm	50 - 100	W Wet
St Stiff	100 - 200	W _p Plastic Limit
VSt Very Stiff	200 - 400	W _L Liquid Limit
H Hard	>400	
Fb Friable		
Density	V Very Loose	Density Index <15%
L Loose	MD Medium Dense	Density Index 15 - 35%
D Dense	D Dense	Density Index 35 - 65%
VD Very Dense	D Dense	Density Index 65 - 85%
		Density Index 85 - 100%

OT.LIB.1.1.GLB.Log_NON-CORED BOREHOLE - TEST PIT_NEW14P-0046 LOGS.24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datagel Lab and In Situ Tool



ENGINEERING LOG - BOREHOLE

CLIENT: MCCLOY SINGLETON PTY LTD

PROJECT: PROPOSED RESIDENTIAL SUBDIVISION - STAGE 1

LOCATION: MAISON DIEU ROAD, SINGLETON

BOREHOLE NO: **BHQ19**

PAGE: 1 OF 1

JOB NO: NEW14P-0046

LOGGED BY: BE

DATE: 3/12/24

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER ATTACHEMENT SURFACE RL:
BOREHOLE DIAMETER: 300 mm DATUM:

Drilling and Sampling				Material description and profile information					Field Test		Structure and additional observations			
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics, colour, minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type		Result		
AD/T	Not Encountered	0.80m		0.5		CI	FILL: Sandy CLAY - medium plasticity, brown, with some grey-brown, fine to medium grained sand, trace pale grey and orange.	M > W _p	VSt	HP	350	FILL: CONTROLLED		
		U50 0.95m		1.0						HP	320			
		1.40m		1.5						HP	350			
		U50 1.60m		2.0						HP	190 - 320			
				2.0						HP	210			
				2.0						HP	220			
				2.0						VSt	HP		220	
				2.0						HP	300			
				2.5						M < W _p	H		HP	420
											2.60m			Hole Terminated at 2.60 m

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distinct strata change

Notes, Samples and Tests

- U₅₀ 50mm Diameter tube sample
- CBR Bulk sample for CBR testing
- E Environmental sample (Glass jar, sealed and chilled on site)
- ASS Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
- B Bulk Sample

Field Tests

- PID Photoionisation detector reading (ppm)
- DCP(x-y) Dynamic penetrometer test (test depth interval shown)
- HP Hand Penetrometer test (UCS kPa)

Consistency	UCS (kPa)
VS Very Soft	<25
S Soft	25 - 50
F Firm	50 - 100
St Stiff	100 - 200
VSt Very Stiff	200 - 400
H Hard	>400
Fb Friable	

Moisture Condition	Density
D Dry	Density Index <15%
M Moist	Density Index 15 - 35%
W Wet	Density Index 35 - 65%
W _p Plastic Limit	Density Index 65 - 85%
W _L Liquid Limit	Density Index 85 - 100%

OT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW14P-0046 LOGS 24.11.05.GPJ <<DrawingFile>> 14/01/2025 14:50 10.03.00.09 Datgel Lab and In Situ Tool

APPENDIX B:

Results of Laboratory Testing

Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181A
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 06/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ01 - (0.40 - 0.58m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	2.6
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	3.8
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	17.5

Swell Test

Initial Pocket Penetrometer (kPa)	450
Final Pocket Penetrometer (kPa)	270
Initial Moisture Content (%)	17.9
Final Moisture Content (%)	22.6
Swell (%)	1.6

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181B
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 06/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ01 - (1.00 - 1.20m)
Material: Silty Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	2.6
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	3.2
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	17.3

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	160
Initial Moisture Content (%)	17.9
Final Moisture Content (%)	24.5
Swell (%)	2.8

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181C
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPO2 - (0.40 - 0.55m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

B. Cullen

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

I_{ss} (%)	3.0
Visual Description	Clay
* Shrink Swell Index (I _{ss}) reported as the percentage vertical strain per pF change in suction.	


Core Shrinkage Test

Shrinkage Strain - Oven Dried (%)	5.4
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	22.3

Swell Test

Initial Pocket Penetrometer (kPa)	250
Final Pocket Penetrometer (kPa)	170
Initial Moisture Content (%)	23.5
Final Moisture Content (%)	25.4
Swell (%)	0.0

* Accreditation does not cover the performance of pocket penetrometer readings.



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181D
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ02 - (1.10 - 1.30m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	2.1
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	3.2
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	18.3

Swell Test

Initial Pocket Penetrometer (kPa)	260
Final Pocket Penetrometer (kPa)	140
Initial Moisture Content (%)	18.5
Final Moisture Content (%)	24.2
Swell (%)	1.1

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181E
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPO3 - (0.40 - 0.55m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	0.2
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	


Core Shrinkage Test

Shrinkage Strain - Oven Dried (%)	0.4
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	10.3

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	160
Initial Moisture Content (%)	10.5
Final Moisture Content (%)	21.7
Swell (%)	-0.1

* Accreditation does not cover the performance of pocket penetrometer readings.



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181F
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ03 - (1.40 - 1.50m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)	
Iss (%)	0.4
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test	
Shrinkage Strain - Oven Dried (%)	0.7
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	11.4

Swell Test	
Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	50
Initial Moisture Content (%)	11.7
Final Moisture Content (%)	23.7
Swell (%)	-0.2
* Accreditation does not cover the performance of pocket penetrometer readings.	



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181G
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ04 - (0.30 - 0.46m)
Material: Sandy Clay
Material Source: On-Site Insitu

Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686



Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.3
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.7
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	15.2

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	110
Initial Moisture Content (%)	15.8
Final Moisture Content (%)	24.3
Swell (%)	1.1

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181H
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ04 - (1.00 - 1.15m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

B. Cullen

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	0.8
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.0
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	12.8

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	150
Initial Moisture Content (%)	13.8
Final Moisture Content (%)	22.7
Swell (%)	1.0

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-71811
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ05 - (0.50 - 0.67m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

I_{ss} (%)	3.7
Visual Description	Clay
* Shrink Swell Index (I _{ss}) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	6.1
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	23.9

Swell Test

Initial Pocket Penetrometer (kPa)	300
Final Pocket Penetrometer (kPa)	200
Initial Moisture Content (%)	22.7
Final Moisture Content (%)	27.1
Swell (%)	1.1

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181J
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ05 - (1.30 - 1.45m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.3
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.0
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	14.0

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	230
Initial Moisture Content (%)	14.3
Final Moisture Content (%)	21.0
Swell (%)	0.8

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181K
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ06 - (0.50 - 0.65m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	0.6
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	0.6
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	12.2

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	180
Initial Moisture Content (%)	12.5
Final Moisture Content (%)	21.7
Swell (%)	0.8

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181L
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 07/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ06 - (1.40 - 1.55m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	0.9
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.2
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	12.2

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	400
Initial Moisture Content (%)	11.8
Final Moisture Content (%)	18.6
Swell (%)	0.9

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181M
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 11/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ07 - (0.40 - 0.57m)
Material: Silty Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

B. Cullen

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	3.0
Visual Description	Silty Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.3
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	16.3

Swell Test

Initial Pocket Penetrometer (kPa)	510
Final Pocket Penetrometer (kPa)	90
Initial Moisture Content (%)	16.0
Final Moisture Content (%)	31.3
Swell (%)	8.4

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181N
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 11/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ07 - (0.80 - 1.00m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.7
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.4
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	16.1

Swell Test

Initial Pocket Penetrometer (kPa)	380
Final Pocket Penetrometer (kPa)	230
Initial Moisture Content (%)	15.6
Final Moisture Content (%)	20.2
Swell (%)	1.4

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181O
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ08 - (0.40 - 0.55m)
Material: Gravelly Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Atterberg Limit (AS1289 3.1.1 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	35		
Plastic Limit (%)	20		
Plasticity Index (%)	15		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.1		
Linear Shrinkage (%)	5.0		
Cracking Crumbling Curling	Cracking		

Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181P
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ08 - (1.70 - 2.00m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.1
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.3
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	Yes
Moisture Content (%)	10.9

Swell Test

Initial Pocket Penetrometer (kPa)	380
Final Pocket Penetrometer (kPa)	500
Initial Moisture Content (%)	11.1
Final Moisture Content (%)	19.8
Swell (%)	1.4

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181Q
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 11/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ09 - (0.50 - 0.65m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	2.1
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.6
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	15.8

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	300
Initial Moisture Content (%)	15.5
Final Moisture Content (%)	19.4
Swell (%)	2.2

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181R
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 11/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ09 - (0.70 - 0.90m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.4
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.9
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	13.8

Swell Test

Initial Pocket Penetrometer (kPa)	
Final Pocket Penetrometer (kPa)	320
Initial Moisture Content (%)	13.4
Final Moisture Content (%)	19.3
Swell (%)	1.2

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181S
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 12/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ10 - (0.30 - 0.57m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	2.5
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	3.9
Estimated % by volume of significant inert inclusions	3
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	16.1

Swell Test

Initial Pocket Penetrometer (kPa)	580
Final Pocket Penetrometer (kPa)	320
Initial Moisture Content (%)	16.3
Final Moisture Content (%)	19.6
Swell (%)	1.2

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report



Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Sample Number: NEW24S-7181T
Date Sampled: 05/11/2024
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: TPQ10 - (1.00 - 1.15m)
Material: Sandy Clay
Material Source: On-Site Insitu

Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

I_{ss} (%)	1.7
Visual Description	Sandy Clay
* Shrink Swell Index (I _{ss}) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.3
Estimated % by volume of significant inert inclusions	3
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	12.2

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	280
Initial Moisture Content (%)	12.8
Final Moisture Content (%)	19.4
Swell (%)	3.5

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7181A	NEW24S-7181B	NEW24S-7181C	NEW24S-7181D	NEW24S-7181E
Date Sampled	05/11/2024	05/11/2024	05/11/2024	05/11/2024	05/11/2024
Date Tested	06/11/2024	06/11/2024	07/11/2024	07/11/2024	07/11/2024
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu
Sample Location	TPQ01 - (0.40 - 0.58m)	TPQ01 - (1.00 - 1.20m)	TPQ02 - (0.40 - 0.55m)	TPQ02 - (1.10 - 1.30m)	TPQ03 - (0.40 - 0.55m)
Inert Material Estimate (%)	1	1	1	1	2
Pocket Penetrometer before (kPa)	450	>600	250	260	>600
Pocket Penetrometer after (kPa)	270	160	170	140	160
Shrinkage Moisture Content (%)	17.5	17.3	22.3	18.3	10.3
Shrinkage (%)	3.8	3.2	5.4	3.2	0.4
Swell Moisture Content Before (%)	17.9	17.9	23.5	18.5	10.5
Swell Moisture Content After (%)	22.6	24.5	25.4	24.2	21.7
Swell (%)	1.6	2.8	0.0	1.1	-0.1
Shrink Swell Index Iss (%)	2.6	2.6	3.0	2.1	0.2
Visual Description	Clay	Clay	Clay	Clay	Clay
Cracking	UC	SC	UC	SC	SC
Crumbling	No	No	No	No	No
Remarks	**	**	**	**	**

Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.

Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.

NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report



Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received

Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



B. Cullen

Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7181F	NEW24S-7181G	NEW24S-7181H	NEW24S-7181I	NEW24S-7181J
Date Sampled	05/11/2024	05/11/2024	05/11/2024	05/11/2024	05/11/2024
Date Tested	07/11/2024	07/11/2024	07/11/2024	07/11/2024	07/11/2024
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu
Sample Location	TPQ03 - (1.40 - 1.50m)	TPQ04 - (0.30 - 0.46m)	TPQ04 - (1.00 - 1.15m)	TPQ05 - (0.50 - 0.67m)	TPQ05 - (1.30 - 1.45m)
Inert Material Estimate (%)	1	2	2	1	2
Pocket Penetrometer before (kPa)	>600	>600	>600	300	>600
Pocket Penetrometer after (kPa)	50	110	150	200	230
Shrinkage Moisture Content (%)	11.4	15.2	12.8	23.9	14.0
Shrinkage (%)	0.7	1.7	1.0	6.1	2.0
Swell Moisture Content Before (%)	11.7	15.8	13.8	22.7	14.3
Swell Moisture Content After (%)	23.7	24.3	22.7	27.1	21.0
Swell (%)	-0.2	1.1	1.0	1.1	0.8
Shrink Swell Index Iss (%)	0.4	1.3	0.8	3.7	1.3
Visual Description	Clay	Sandy Clay	Sandy Clay	Clay	Clay
Cracking	SC	SC	SC	UC	SC
Crumbling	No	No	No	No	No
Remarks	**	**	**	**	**

Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.
 Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.
 NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7181K	NEW24S-7181L	NEW24S-7181M	NEW24S-7181N	NEW24S-7181P
Date Sampled	05/11/2024	05/11/2024	05/11/2024	05/11/2024	05/11/2024
Date Tested	07/11/2024	07/11/2024	11/11/2024	11/11/2024	13/11/2024
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu
Sample Location	TPQ06 - (0.50 - 0.65m)	TPQ06 - (1.40 - 1.55m)	TPQ07 - (0.40 - 0.57m)	TPQ07 - (0.80 - 1.00m)	TPQ08 - (1.70 - 2.00m)
Inert Material Estimate (%)	2	1	2	1	1
Pocket Penetrometer before (kPa)	>600	>600	510	380	380
Pocket Penetrometer after (kPa)	180	400	90	230	500
Shrinkage Moisture Content (%)	12.2	12.2	16.3	16.1	10.9
Shrinkage (%)	0.6	1.2	1.3	2.4	1.3
Swell Moisture Content Before (%)	12.5	11.8	16.0	15.6	11.1
Swell Moisture Content After (%)	21.7	18.6	31.3	20.2	19.8
Swell (%)	0.8	0.9	8.4	1.4	1.4
Shrink Swell Index Iss (%)	0.6	0.9	3.0	1.7	1.1
Visual Description	Sandy Clay	Clay	Silty Clay	Sandy Clay	Clay
Cracking	SC	SC	MC	SC	SC
Crumbling	No	No	No	No	Yes
Remarks	**	**	**	**	**

Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.

Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.

NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report

Report Number: NEW14P-0046-1
Issue Number: 1
Date Issued: 09/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7181
Dates Tested: 06/11/2024 - 13/11/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7181Q	NEW24S-7181R	NEW24S-7181S	NEW24S-7181T	
Date Sampled	05/11/2024	05/11/2024	05/11/2024	05/11/2024	
Date Tested	11/11/2024	11/11/2024	12/11/2024	13/11/2024	
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	
Sample Location	TPQ09 - (0.50 - 0.65m)	TPQ09 - (0.70 - 0.90m)	TPQ10 - (0.30 - 0.57m)	TPQ10 - (1.00 - 1.15m)	
Inert Material Estimate (%)	2	1	3	3	
Pocket Penetrometer before (kPa)	>600	**	580	>600	
Pocket Penetrometer after (kPa)	300	320	320	280	
Shrinkage Moisture Content (%)	15.8	13.8	16.1	12.2	
Shrinkage (%)	2.6	1.9	3.9	1.3	
Swell Moisture Content Before (%)	15.5	13.4	16.3	12.8	
Swell Moisture Content After (%)	19.4	19.3	19.6	19.4	
Swell (%)	2.2	1.2	1.2	3.5	
Shrink Swell Index Iss (%)	2.1	1.4	2.5	1.7	
Visual Description	Sandy Clay	Sandy Clay	Sandy Clay	Sandy Clay	
Cracking	SC	SC	UC	SC	
Crumbling	No	No	No	No	
Remarks	**	**	**	**	

Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.

Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.

NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782A
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ11 - (0.40 - 0.60m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.9
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	3.0
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	18.5

Swell Test

Initial Pocket Penetrometer (kPa)	450
Final Pocket Penetrometer (kPa)	230
Initial Moisture Content (%)	18.1
Final Moisture Content (%)	21.5
Swell (%)	0.9

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782B
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ11 - (1.00 - 1.15m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing




Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)	
Iss (%)	1.8
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test	
Shrinkage Strain - Oven Dried (%)	2.5
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	17.1

Swell Test	
Initial Pocket Penetrometer (kPa)	430
Final Pocket Penetrometer (kPa)	230
Initial Moisture Content (%)	17.6
Final Moisture Content (%)	20.6
Swell (%)	1.6
* Accreditation does not cover the performance of pocket penetrometer readings.	



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782C
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ12 - (0.45 - 0.60m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.2
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.3
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	17.3

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	350
Initial Moisture Content (%)	17.0
Final Moisture Content (%)	22.1
Swell (%)	1.8

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782D
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ12 - (1.10 - 1.30m)
Material: Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.2
Visual Description	Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.4
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	16.0

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	270
Initial Moisture Content (%)	16.0
Final Moisture Content (%)	20.2
Swell (%)	1.7

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782E
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ13 - (0.50 - 0.64m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.9
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.0
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	Yes
Moisture Content (%)	14.5

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	310
Initial Moisture Content (%)	14.2
Final Moisture Content (%)	22.2
Swell (%)	2.9

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782F
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ14 - (0.40 - 0.56m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

I_{ss} (%)	2.0
Visual Description	Sandy Clay
* Shrink Swell Index (I _{ss}) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.3
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	12.9

Swell Test

Initial Pocket Penetrometer (kPa)	480
Final Pocket Penetrometer (kPa)	170
Initial Moisture Content (%)	13.1
Final Moisture Content (%)	19.9
Swell (%)	2.7

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782G
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 13/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ14 - (1.10 - 1.30m)
Material: Silty Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Atterberg Limit (AS1289 3.1.1 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	48		
Plastic Limit (%)	16		
Plasticity Index (%)	32		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.1		
Linear Shrinkage (%)	12.5		
Cracking Crumbling Curling	Cracking		

Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782H
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 10/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ15 - (0.60 - 0.75m)
Material: Silty Clay
Material Source: On-Site Insitu

Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468

Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



B. Cullen

Approved Signatory: Brent Cullen

Engineering Geologist

NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	0.8
Visual Description	Silty Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	


Core Shrinkage Test

Shrinkage Strain - Oven Dried (%)	1.5
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	Yes
Moisture Content (%)	10.5

Swell Test

Initial Pocket Penetrometer (kPa)	180
Final Pocket Penetrometer (kPa)	60
Initial Moisture Content (%)	12.0
Final Moisture Content (%)	25.0
Swell (%)	-0.3

* Accreditation does not cover the performance of pocket penetrometer readings.



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782I
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 11/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ16 - (0.50 - 0.65m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.9
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	3.2
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	Yes
Moisture Content (%)	16.6

Swell Test

Initial Pocket Penetrometer (kPa)	470
Final Pocket Penetrometer (kPa)	160
Initial Moisture Content (%)	16.7
Final Moisture Content (%)	21.5
Swell (%)	0.6

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782J
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 11/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ16 - (1.00 - 1.15m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.3
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.9
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	12.7

Swell Test

Initial Pocket Penetrometer (kPa)	530
Final Pocket Penetrometer (kPa)	90
Initial Moisture Content (%)	13.6
Final Moisture Content (%)	27.2
Swell (%)	1.0

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782K
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 11/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ17 - (0.50 - 0.65m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.1
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.7
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	13.2

Swell Test

Initial Pocket Penetrometer (kPa)	590
Final Pocket Penetrometer (kPa)	310
Initial Moisture Content (%)	13.2
Final Moisture Content (%)	17.6
Swell (%)	0.8

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782L
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 11/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ17 - (1.00 - 1.20m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.9
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.8
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	16.8

Swell Test

Initial Pocket Penetrometer (kPa)	360
Final Pocket Penetrometer (kPa)	250
Initial Moisture Content (%)	16.6
Final Moisture Content (%)	22.0
Swell (%)	1.1

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782M
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ18 - (0.50 - 0.65m)
Material: Gravelly Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.9
Visual Description	Gravelly Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.0
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	14.6

Swell Test

Initial Pocket Penetrometer (kPa)	430
Final Pocket Penetrometer (kPa)	260
Initial Moisture Content (%)	13.9
Final Moisture Content (%)	21.2
Swell (%)	3.0

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782N
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ18 - (1.00 - 1.15m)
Material: Gravelly Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	0.9
Visual Description	Gravelly Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	1.0
Estimated % by volume of significant inert inclusions	2
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	14.3

Swell Test

Initial Pocket Penetrometer (kPa)	>600
Final Pocket Penetrometer (kPa)	210
Initial Moisture Content (%)	15.0
Final Moisture Content (%)	21.2
Swell (%)	1.3

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782O
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ19 - (0.80 - 0.95m)
Material: Sandy Clay
Material Source: On-Site Insitu



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)

Iss (%)	1.7
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test


Shrinkage Strain - Oven Dried (%)	2.1
Estimated % by volume of significant inert inclusions	1
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	17.8

Swell Test

Initial Pocket Penetrometer (kPa)	350
Final Pocket Penetrometer (kPa)	130
Initial Moisture Content (%)	18.1
Final Moisture Content (%)	26.3
Swell (%)	1.9

* Accreditation does not cover the performance of pocket penetrometer readings.

Shrink Swell Index



Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7782A	NEW24S-7782B	NEW24S-7782C	NEW24S-7782D	NEW24S-7782E
Date Sampled	03/12/2024	03/12/2024	03/12/2024	03/12/2024	03/12/2024
Date Tested	10/12/2024	10/12/2024	10/12/2024	10/12/2024	10/12/2024
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu
Sample Location	BHQ11 - (0.40 - 0.60m)	BHQ11 - (1.00 - 1.15m)	BHQ12 - (0.45 - 0.60m)	BHQ12 - (1.10 - 1.30m)	BHQ13 - (0.50 - 0.64m)
Inert Material Estimate (%)	1	1	1	1	1
Pocket Penetrometer before (kPa)	450	430	>600	>600	>600
Pocket Penetrometer after (kPa)	230	230	350	270	310
Shrinkage Moisture Content (%)	18.5	17.1	17.3	16.0	14.5
Shrinkage (%)	3.0	2.5	1.3	1.4	2.0
Swell Moisture Content Before (%)	18.1	17.6	17.0	16.0	14.2
Swell Moisture Content After (%)	21.5	20.6	22.1	20.2	22.2
Swell (%)	0.9	1.6	1.8	1.7	2.9
Shrink Swell Index Iss (%)	1.9	1.8	1.2	1.2	1.9
Visual Description	Clay	Clay	Sandy Clay	Clay	Sandy Clay
Cracking	SC	SC	SC	SC	SC
Crumbling	No	No	No	No	Yes
Remarks	**	**	**	**	**

Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.

Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.

NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7782F	NEW24S-7782H	NEW24S-7782I	NEW24S-7782J	NEW24S-7782K
Date Sampled	03/12/2024	03/12/2024	03/12/2024	03/12/2024	03/12/2024
Date Tested	10/12/2024	10/12/2024	11/12/2024	11/12/2024	11/12/2024
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu
Sample Location	BHQ14 - (0.40 - 0.56m)	BHQ15 - (0.60 - 0.75m)	BHQ16 - (0.50 - 0.65m)	BHQ16 - (1.00 - 1.15m)	BHQ17 - (0.50 - 0.65m)
Inert Material Estimate (%)	1	1	1	1	1
Pocket Penetrometer before (kPa)	480	180	470	530	590
Pocket Penetrometer after (kPa)	170	60	160	90	310
Shrinkage Moisture Content (%)	12.9	10.5	16.6	12.7	13.2
Shrinkage (%)	2.3	1.5	3.2	1.9	1.7
Swell Moisture Content Before (%)	13.1	12.0	16.7	13.6	13.2
Swell Moisture Content After (%)	19.9	25.0	21.5	27.2	17.6
Swell (%)	2.7	-0.3	0.6	1.0	0.8
Shrink Swell Index Iss (%)	2.0	0.8	1.9	1.3	1.1
Visual Description	Sandy Clay	Silty Clay	Sandy Clay	Sandy Clay	Sandy Clay
Cracking	UC	SC	SC	SC	UC
Crumbling	No	Yes	Yes	No	No
Remarks	**	**	**	**	**

Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.

Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.

NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report

Report Number: NEW14P-0046-2
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received



Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Brent Cullen
 Engineering Geologist
 NATA Accredited Laboratory Number: 18686

Shrink Swell Index AS 1289 7.1.1 & 2.1.1					
Sample Number	NEW24S-7782L	NEW24S-7782M	NEW24S-7782N	NEW24S-7782O	
Date Sampled	03/12/2024	03/12/2024	03/12/2024	03/12/2024	
Date Tested	11/12/2024	12/12/2024	12/12/2024	12/12/2024	
Material Source	On-Site Insitu	On-Site Insitu	On-Site Insitu	On-Site Insitu	
Sample Location	BHQ17 - (1.00 - 1.20m)	BHQ18 - (0.50 - 0.65m)	BHQ18 - (1.00 - 1.15m)	BHQ19 - (0.80 - 0.95m)	
Inert Material Estimate (%)	1	1	2	1	
Pocket Penetrometer before (kPa)	360	430	>600	350	
Pocket Penetrometer after (kPa)	250	260	210	130	
Shrinkage Moisture Content (%)	16.8	14.6	14.3	17.8	
Shrinkage (%)	2.8	2.0	1.0	2.1	
Swell Moisture Content Before (%)	16.6	13.9	15.0	18.1	
Swell Moisture Content After (%)	22.0	21.2	21.2	26.3	
Swell (%)	1.1	3.0	1.3	1.9	
Shrink Swell Index I _{ss} (%)	1.9	1.9	0.9	1.7	
Visual Description	Sandy Clay	Gravelly Sandy Clay	Gravelly Sandy Clay	Sandy Clay	
Cracking	SC	SC	SC	SC	
Crumbling	No	No	No	No	
Remarks	**	**	**	**	

Shrink Swell Index (I_{ss}) reported as the percentage vertical strain per pF change in suction.

Cracking Terminology: UC Uncracked, SC Slightly Cracked, MC Moderately Cracked, HC Highly Cracked, FR Fragmented.

NATA Accreditation does not cover the performance of pocket penetrometer readings.

Material Test Report




Report Number: NEW14P-0046-2A
Issue Number: 1
Date Issued: 18/12/2024
Client: McCloy Singleton Pty Ltd
 Suite 2, Ground Floor, 317 Hunter Street, Newcastle NSW 2300
Project Number: NEW14P-0046
Project Name: Proposed Subdivision - The Fairways, Stage 1 & 2
Project Location: Maison Dieu Road, Singleton, NSW
Work Request: 7782
Sample Number: NEW24S-7782P
Client Sample #: REMOULD
Date Sampled: 03/12/2024
Dates Tested: 05/12/2024 - 12/12/2024
Sampling Method: Sampled by Engineering Department
The results apply to the sample as received
Sample Location: BHQ19 - (1.40 - 1.60m)
Material: Sandy Clay
Material Source: On-Site Insitu

Newcastle Laboratory
 2 Murray Dwyer Circuit Mayfield West NSW 2304
 Phone: (02) 4968 4468
 Email: brentcullen@qualtest.com.au

Brent Cullen (Engineering Geologist)

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)	
Iss (%)	2.1
Visual Description	Sandy Clay
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	
Sample remoulded at estimated OMC and approximately 98% Standard Compaction	
Core Shrinkage Test	
Shrinkage Strain - Oven Dried (%)	2.6
Estimated % by volume of significant inert inclusions	1
Cracking	Uncracked
Crumbling	No
Moisture Content (%)	15.9
Swell Test	
Initial Pocket Penetrometer (kPa)	530
Final Pocket Penetrometer (kPa)	230
Initial Moisture Content (%)	16.7
Final Moisture Content (%)	20.0
Swell (%)	2.5
* Accreditation does not cover the performance of pocket penetrometer readings.	

Shrink Swell Index



APPENDIX C:

CSIRO Sheet BTF 18

**Foundation Maintenance and Footing
Performance: A Homeowner's Guide**

Foundation Maintenance and Footing Performance: A Homeowner's Guide



CSIRO

BTF 18
replaces
Information
Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups – granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take place because of the expulsion of moisture from the soil or because of the soil's lack of resistance to local compressive or shear stresses. This will usually take place during the first few months after construction, but has been known to take many years in exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation

This is particularly a problem in clay soils. Saturation creates a bog-like suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume – particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

GENERAL DEFINITIONS OF SITE CLASSES

Class	Foundation
A	Most sand and rock sites with little or no ground movement from moisture changes
S	Slightly reactive clay sites with only slight ground movement from moisture changes
M	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes
H	Highly reactive clay sites, which can experience high ground movement from moisture changes
E	Extremely reactive sites, which can experience extreme ground movement from moisture changes
A to P	Filled sites
P	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways:

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- Differing compaction of foundation soil prior to construction.
- Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear failure.

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sun's heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpend).


Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of cornice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself

Most forces that the soil causes to be exerted on structures are vertical – i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the vertical member of the frame.

Effects on full masonry structures

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated seriously.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred.

The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken rubble is used as fill. Water that runs along these trenches can be responsible for serious erosion, interstrata seepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

- Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.

It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.


Protection of the building perimeter

It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most serious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

CLASSIFICATION OF DAMAGE WITH REFERENCE TO WALLS

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage category
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	<5 mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5–15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15–25 mm but also depend on number of cracks	4



- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient ventilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.

Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia

Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au

Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited